



GOVERNMENT OF ARUNACHAL PRADESH  
OFFICE OF THE SUPERINTENDENT OF POLICE (TELECOM)  
CHIMPU : ITANAGAR


No. PHQ/WT/PP-66/SAP/2025-26/2025

Dated : Itanagar the 17<sup>th</sup> April '2026.**CORRIGENDUM - II**

With reference to Pre-Bid meeting held at PHQ, Itanagar, Arunachal Pradesh on 16/04/2026 (1100 Hr) wrt Tender Notice No. PHQ/WT/PP-66/SAP/2025-26/2025 dated 20/05/2026 against Incident Command & Control Vehicle (ICCV), the following clarifications has been issued which are as under :

Sl.	Tender Clause	Points requested by the Firm	Clarification from department
1	General Instructions Point #18, Page NO:4 18. Successful tenderers have to supply the ICCV within 06 months with complete setup from the date of issue of Supply Order. Failing which, 5% of the Security Deposit will be forfeited and the Supply Order will be cancelled OR a sum equivalent to 0.5% of the delivery price of the delayed items for each week of delay or part thereof beyond the original contract delivery period will be recovered, subject to a maximum of 10% as liquidated damages.	The stipulated delivery timeline of 6 months for supply of ICCV with complete setup is not feasible considering the lead time required for electronic components, vehicle chassis procurement, and fabrication activities. In view of this, it is requested to extend the delivery timeline to a minimum of 9 months. Kindly confirm.	Committee agreed to extend the timeline by 08 months as requested by the firm in view of Gazette Notification issued by Government of India related to quality testing of CCTV Camera/VSS Software etc. and time required for fabrication activities.
2	1. Technical Specifications S.No IV. Page 6. 4 The ICCV shall be built on a vehicle chassis having a wheelbase more than 2900mm and an overall vehicle length not exceeding 5.5m. The vehicle shall be provided with seating arrangements for three operators for CCTV and communication operation with adequate storage facilities. ICCV shall have a 32" displays for CCTV Live feed	The wheelbase and overall vehicle length specified in this clause appear to be inconsistent with the chassis technical specifications mentioned on Page No. 7. Kindly clarify the correct requirement.	The Committee clarified that the error made in typing is corrected to read as "minimum 3050 mm" in place of "2900 mm".
3	2. CHASSIS & CUSTOM DESIGN, FABRICATION AND BUILD-UP OF ICCV, Page No: 7, S.No A. I & III I. Wheelbase: Minimum 3050mm III. Overall Length: minimum 5135mm	The wheelbase and overall vehicle length specified in this clause appear to be inconsistent with the chassis technical specifications mentioned on Page No.6. Kindly clarify the correct requirement.	- do -
4	7. MIL GRADE MAST MOUNTED VEHICLE OUTDOOR CAMERA page No:9	As per the Essential Requirements (ER) of the Standardisation Testing and Quality Certification Directorate (STQC) for CCTV systems, all cameras are required to be STQC certified. However, most OEMs are currently in the process of certification, and the models already certified are not suitable for vehicle-mounted applications. The certification process typically takes 9-12 months. In view of this, it is requested to allow an additional 3 weeks to identify compliant OEMs or to consider suitable amendments to the specification. Ref: 1. STQC ER for CCTV Systems (under MeitY, Government of India) 2. "Essential Requirements for Security Certification of CCTV Systems" issued by STQC Directorate	The Committee has already accorded approval for the extension of the timeline by 08 (eight) months as Sl.No.1 which is for all activities involved in fabrication /certifications.

Sl.	Tender Clause	Points requested by the Firm	Clarification from department
5	8. Fixed Outdoor Cameras mounted on ICCV.	As per the Essential Requirements (ER) of the Standardisation Testing and Quality Certification Directorate (STQC) for CCTV systems, all cameras are required to be STQC certified. However, most OEMs are currently in the process of certification, and the models already certified are not suitable for vehicle-mounted applications. The certification process typically takes 9–12 months. In view of this, it is requested to allow an additional 3 weeks to identify compliant OEMs or to consider suitable amendments to the specification. Ref: 1. STQC ER for CCTV Systems (under MeitY, Government of India) 2. "Essential Requirements for Security Certification of CCTV Systems" issued by STQC Directorate	The Committee has already accorded approval for the extension of the timeline by 08 (eight) months as Sl.No.1 which is for all activities involved in fabrication /certifications.
6	9. FIXED DEPLOYABLE BATTERY POWERED WIRELESS CLOS CAMERAS	As per the Essential Requirements (ER) of the Standardisation Testing and Quality Certification Directorate (STQC) for CCTV systems, all cameras are required to be STQC certified. However, most OEMs are currently in the process of certification, and the models already certified are not suitable for vehicle-mounted applications. The certification process typically takes 9–12 months. In view of this, it is requested to allow an additional 3 weeks to identify compliant OEMs or to consider suitable amendments to the specification. Ref: 1. STQC ER for CCTV Systems (under MeitY, Government of India) 2. "Essential Requirements for Security Certification of CCTV Systems" issued by STQC Directorate	The Committee has already accorded approval for the extension of the timeline by 08 (eight) months as Sl.No.1 which is for all activities involved in fabrication /certifications.
7	Minimum Bill of Material SI #1, page 21. Chassis - Wheelbase 2900mm or higher, Length-Minimum-550mm	The wheelbase and overall vehicle length specified in this clause appear to be inconsistent with the chassis technical specifications mentioned on Page No. 6 & 7. Kindly clarify the correct requirement.	The Committee clarified that the error made in typing is corrected to read as "minimum 3050 mm" in place of "2900 mm".
8	Minimum Bill of Material SI #2, page 21. Driver, Operator, Conference Area	The ICCV configuration specifies seating for three operators. However, the inclusion of a conference area is also mentioned. Kindly clarify whether a conference area is required. Considering the vehicle size constraints, accommodating a conference area may not be feasible. Please clarify	The Committee has removed the "conference area" considering the size of the vehicle.
	Minimum Bill of Material SI #6, page 21. Telescopic Pneumatic Mast for Radio/WI-FI Antenna, PTZ Camera & LED Flood Lights	No specifications have been provided for the LED flood lights. Additionally, accommodating the Wi-Fi antenna, PTZ camera, and LED flood lights on a single telescopic mast may not be feasible. It is assumed that the Wi-Fi antenna and PTZ camera are to be mounted on the mast. Kindly clarify the exact requirement.	Committee clarify that LED flood lights will be of 150 Watt. It has been further clarified it will be mounted on same Telescopic Mast.

  
 21/4  
 Superintendent of Police(Telecom)  
 Chimpu,Itanagar,  
 Arunachal Pradesh,  
 Dated : Itanagar, the 17<sup>th</sup> April '2026  
 Arunachal Pradesh

Memo. No. PHQ/WT/PP-66/SAP/2025-26/2025

Copy to:

- ✓ 1. I/C Computer Cell, PHQ, Itanagar for uploading in Arunachal Pradesh Police website.
2. Office copy.

Superintendent of Police(Telecom)  
 Chimpu ,Itanagar,  
 Arunachal Pradesh.